Constructing a latrine to the Travellers' Bungalow at Yeslurpet.

No.	Items of work	Per	Quantity
1	Earthwork excavation	C. yd.	4
2	Burnt stone in mortar	C. ft.	113
3	Burnt brick in mortar	Do	249
4	Constructing seats with cement plastering	L. S.	Rs.
5	Burnt stone slabs 6" thick	S. ft.	5
6	Jungle wood work wrought and put up	C. ft.	4·02
7	Coping 9" burnt brick in chunam with plastering	R. ft.	8
8	Cornice work 6"	Do	26
9	Honne wood cross pieces for ventilators	L. S.	L. S.
10	Roofing with 1st class Mangalore tiles and teak reepers	Sq.	0·93
11	Chunam plastering	Sq.	4·82
12	White and colourwashing	Do	4·19
13	Tarring	L. S.	5
14	Constructing surki drain and cement plastering	L. S.	10
15	Flooring with concrete in mortar 3" and cement plastering	Sq.	0·33
	Sinking a well in the compound	L. S.	Rs.

K. NARYANA IYENGAR,
Ex. Engr. Hassan Division.

CHITALDRUG DIVISION.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 5th November 1920, for restoring the Gudanurahalli large minor tank Registered No. 2 of Hiriyur Taluk, Chitaldurg District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Gudanurahalli large minor tank, Registered No. 2 of Hiriyur Taluk, Chitaldrug District, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Gudanurahalli large minor tank, Registered No. 2 of Hiriyur Taluk, Chitaldrug District.

No.	Items of work	Quantity	
	Bund—		
1	Earthwork with watering, tamping, etc.; complete ...	C. yd.	2,819
2	Providing new stone revetment with new jelly, backing ...	C. yd.	609
3	New grade stones with figures cut and painted	No.	24
4	New top width stones	No.	24
5	Providing new gauge stone with figures cut and painted ...	No.	1
6	Providing new bench mark stones with figures and painting	No.	1
	Sluice—		
7	Cutting open the bund and examining and repairing the sluice including refilling.	L. S.	Rs.
	Weir—		
8	Earthwork excavation hard soil	C. yd.	1,035
9	Pitching rough stone apron	C. yd	292⅓
10	Burnt stone toe slabs	S. ft.	390

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 5th November 1920, for constructing a kitchen to the travellers' bungalow at Molakalmuru, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 100 in cash, or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a kitchen to the travellers' bungalow at Molakalmuru, Chitaldrug District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT FORM.

For constructing a kitchen to the Travellers' Bungalow at Molakalmuru.

No.	Item of work	Quantity	
		Unit	
1	Earthwork excavation and filling in basement	100 cft.	4·21
2	Burnt stone in chunam. Foundation and basement ...	100 cft.	5·69
3	Burnt brick in chunam	Do	1·97
4	Burnt brick in clay	Do	8·49
5	Burnt brick archwork	Do.	0·10
6	Burnt stone slabs dressed and fixed 4" to 6" thick ..	Sft	107
7	Honnewood work wrought and put up	Cft.	37·70
8	Roofing with 1st class Mangalore tiles on teak reapers ...	Sqr.	7·40
9	Ridge tiles set in mortar	Rft.	29
10	Providing and fixing Mangalore ventilating tiles	No.	4
11	Cudappa slabs flooring over 3" concrete bed and cement pointing	Sqr.	2·70
12	Chunam borders 3"×6"	Rft.	42
13	Lime mortar plastering	Sqr.	19·65
14	White and colour washing	Do	19·65
15	Pointing with chunam	Do	1·27
16	Teakwood battened doors with iron work, etc., complete ...	Sft.	101
16(a)	Honnewood Do do	Do	Do
17	Teakwood battened windows	Do	9
17(a)	Honnewood do	Do	Do
18	Do Glazed ventilators	Do	22
18(a)	Teakwood Do	Do	Do
19	Wood-oiling and tarring	L. S.	Rs.
20	Teakwood eave boards (ordinary)	Rft.	110
21	Chocolate painting	Sqr.	3·52
22	Pestle and mortar	L. S.	Rs.
23	Constructing bath and kitchen ovens	No.	2
24	Clearing site and levelling ground	L. S.	Rs.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 20th November 1920, for improving Godabanal-Annehal Tank, Registered No. 38 of Chitaldrug. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1922.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Godabanal-Annehal Tank, Registered No. 38, Chitaldrug Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for Improving Godabanal-Annehal Tank, Reg. No. 38, Chitaldrug Taluk, Chitaldrug District.

Item No.	Items of work	Quantity	
	Bund—		
1	Earthwork to bund including watering and tamping, cutting grips and forming good joints to the base thoroughly cleared	C. yd.	9,032
2	Removing the apron of right weir and utilizing the same for revetment in front	L. S. C. yd.	50
3	Turfing with mani grass	S. yd.	7,070
4	Removing the old revetment and utilizing the same for revetment in front	C. yd.	260
5	New Stone revetment with lead, etc., ...	C. yd.	1,180
6	Removing and refixing grade stones with bed slabs including painting	No.	37
7	Providing new grade stones with bed slabs	,,	3
8	Removing and refixing top width stones	,,	37
9	New bed grade stones	,,	3
10	Removing and refixing gauge stone and painting ...	,,	1
11	Removing and refixing Registered No. stone including painting	,,	1
12	Removing and refixing B. M. Stones	,,	2
13	Providing date stone	,,	1
14	Removing the right weir apron and connecting old and new bund with required sections	L. S.	Rs.
	Sluice—		
15	Marking Gauge on the gibbet stone with cement and raising the gibbet by 3 feet or to R. L. 102·00, 1½' wall with burnt brick in surki mortar and cement plastering, with burnt stone slabs coping and locking arrangements to the plug rod and clearing silt in front of sluice	L. S.	Rs.

Item No.	Items of work	Quantity	
	Weir—		
16	Earthwork excavation and utilizing the earth to wing bund, etc.	C. yd.	315
17	Filling in foundation with surki mortar	C. ft.	2,096
18	Burnt brick in surki mortar	C. ft.	1,600
19	Burnt stone slabs dressed 6" thick with joints, etc., complete	S. ft.	447
20	Plastering with nice surki mortar including watering, etc., complete	Sq.	10·35
21	Rough plastering with surki mortar to toe wall wherever necessary	Sq.	6·00
22	Rough stone apron with jelly and lead, etc.,	C. yd.	390
23	Cement pointing to the joints of coping slabs of body and toe wall	Sq.	6·00
24	Cutting ramps to pass carts over the bund as usual behind the proposed jack bund of weir crossings	L. S.	Rs.
25	Compensation for lands	....	...

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 20th November 1920, for constructing a V. E. School at Asagodu, Jagalur Taluk, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. in cash, or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a V. E. School at Asagodu, Jagalur Taluk, Chitaldrug District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing a V. E. School at Asagodu, Jagalur Taluk, Chitaldrug District.

Item No.	Items of work	Quantity	
1	Earthwork excavation for foundation and filling in basement	100 C. ft.	25·56
2	Chunam concrete	100 C. ft.	7·07

Item No.	Items of work	Quantity	
3	Stone in clay foundation and basement	100 C. ft.	20·55
4	Burnt brick in clay superstructure	Do	25·42
5	Burnt brick in mortar superstructure	Do	4·01
6	Burnt brick in mortar coping	R. ft.	53
7	Caps of gate pillars	No.	2
8	Burnt stone slabs dressed and fixed 6" thick, complete ...	S. ft.	346
9	Burnt stone pillars including cutting grooves, etc., complete.	S. ft.	120
10	Door—Honnewood frames, mango-wood plank, battened shutters with iron works, etc., complete	S. ft.	196
11	Window—Honnewood frames, mango-wood plank, battened shutters with iron works, etc., complete ...	S. ft.	135
12	Honne wood-work wrought and put up	C. ft.	41·37
13	Roofing with pot tiles on bamboo reapers, etc., complete ...	Sq.	22.83
14	Pot tiles ridge set in mortar	R. ft.	79
15	Chunam borders over roof	R. ft.	108
16	Chunam pointing to basement	Sq.	4·23
17	Chunam plastering	Sq.	29·52
18	Mud plastering	Sq.	29·68
19	White and colour washing	Sq.	59·20
20	Tarring to wood-work, and wood-oiling	L. S.	Rs.
21	Flooring with gravel including carting and cow-dung washing, etc., complete	C. yd.	25
22	Honnewood gate with iron work, painting, etc ...	S. ft.	22
23	Chocolate painting	S. ft.	7·67
24	Clearing site and levelling ground	L. S.	Rs.
25	Cornice work for gate pillars	R. ft.	18
26	Black painting for black board	Sq.	8·37
27	Sundry and unforeseen charges	L. S.	Rs.
28	Bamboo rafters	R. ft.	944

Y. ASVATHANARAYANA RAO,
Executive Engineer, Chitaldrug Division

TUMKUR DISTRICT.

District Hospital, Tumkur, dated October 1920.

Notice is hereby given that sealed tenders will be received at the above Hospital *between the hours of 4 P. M. and 5 P. M. on 24th November 1920,* by the District Medical and Sanitary Officer, Tumkur District, for the supply, by contract, of all articles of diets etc., as per annexed list, required for the use of the above Hospital from 1st January 1921 to the end of 31st December 1921.

2. No tenders will be received after the above said hour on the 24th November 1920.

3. Tenders to be superscribed "Tenders for the supply of provision for the District Hospital, Tumkur".

4. No tenders will be received unless accompanied by a deposit of Rs. 50 in cash, currency notes, or Government bonds.

5. All tenders must specify the rates at which the articles can be supplied in pound, weight or in seers per rupee as the case may be.

6. Tenders will be opened by the District Medical and Sanitary Officer at the District Hospital, Tumkur, on the date and hour above noted in the presence of such tenderers as may choose to attend.

7. The quantities stated in the annexed list are not guaranteed.

8. The District Medical and Sanitary Officer reserves to himself the right of rejecting any tender without assigning any reason for so doing.

9. The deposit of the successful competitor will be retained and will be forfeited, if he fails to execute the contract bond or to furnish security to the amount above stated.

10. No advance of cash will be made over to the contractor. Payments for the articles supplied will be made by the District Medical and Sanitary Officer.

11. The contractor must submit his bills in English with vouchers for the cost of all articles supplied with calculation correctly made, *by the 5th of each month.* Persons who are unable to do this need not compete.

12. A store room will be made over to the contractor, in which he can keep all non-perishable articles, of which not less than one month's supply, must always be in store,